OSTÉOPEINTURE

CLIENT	Fiducie Familiale Jean-Pierre Azzopardi	ADDRESS	649 Roslyn Ave. Westmount
PROJECT	AZZOPARDI_02	DATE	Feb 19, 2025

DESCRIPTION OF WORK

HOME MAKEOVER – PHASE 2

OUR PRICE INCLUDES

- Careful protection of all floors and furniture present in the space
- Thorough preparation work on all trim i.e. peel flaking paint, resurface, oil prime varnished wood, and caulk cracks
- Primer anywhere needed and 2 coats of paint on all walls, ceilings, cornices, doors (external faces), windows and all trim
- Clean up at the end of each day, leaving the space clean, livable and comfortable
- Removal and reinstallation of any wall plates and wall hardware
- A respectful, clean and quiet working environment to make the work period smooth for you and your family
- Any major additional repairs will be charged at 75 $/H plus taxes and materials.

STANDARD ITEMIZED PRICING – includes labor and materials	
Walls *– 10 x 15 room size – minor preparation (1H) and painting*	**500 $**
Ceiling *– 10 x 15 room size – painting*	**150 $**
Cornice *– minor preparation (.5H) and painting*	**130 $**
Door and frame *(1 face) – good preparation (1H) and painting*	**135 $**
Window and frame *– good preparation (1.5H) and painting*	**200 $**
Baseboards *– good preparation (1H) and painting*	**200 $**
Overall care *– set up, protection, daily cleaning, final touch ups*	**250 $**

INTERIOR PAINTING & PLASTERING WORK	
Office	**1,200 $**
- Preparation and painting of ceiling, cornice, 2 doors, 1 window, and baseboards	1,100 $
- Includes thorough baseboard repairs (1.5H)	100 $
- Excludes painting of all walls	
Small Bedroom	**1,800 $**
- Preparation and painting of walls, ceiling, cornice, 3 doors, 2 windows, and baseboards	1,650 $
- Includes thorough baseboard and other trim repairs (2H)	150 $
- Excludes potential repairs of cracks on ceiling or walls [0$ - 250$]	[+ 100 $]
2nd Floor Center Space	**2,150 $**
- Preparation and painting of walls, ceiling, cornice, 7 doors, and baseboards	2,150 $
- Excludes repairs: securing plasterboards and resurfacing walls [500$ - 700$]	[+ 600$]
- Excludes replacing shower access door panel and other desired adjustments [150$ - 250 $]	[+ 150$]

Skylight	**1,000 $**
➢ Includes preparation and caulking where needed to mask cracks in trim or walls (2H)	
➢ Includes trim to be painted in semi-gloss finish as the rest of the trim	
Staircase	**1,800 $**
➢ Includes preparation and painting of all 90 spindles	1,000 $
➢ Includes walls, stringers and all previously painted staircase trim	850 $
➢ Excludes repairs of cracks on stringers and walls [250$ - 450$]	[+ 300 $]
Ground Floor Hall	**1,800 $**
➢ Preparation and painting of walls, ceiling, cornice and medallion, 2 doors, 2 doorways and baseboards	1,250 $
➢ Includes the entrance french door and its adjacent windows	400 $
➢ Includes one radiator cover and one full radiator	150 $
Entrance	**1,100 $**
➢ Preparation and painting of walls, ceiling, cornice, baseboards and radiator box	700 $
➢ Includes the entrance french door and its adjacent windows	400 $
➢ Excludes the front door and extra plaster repairs on walls and cornice [500$ - 800$]	[+ 600$]
Side Door Passage and Basement Staircase	**1,300 $**
➢ Preparation and painting of walls, ceiling, cornice, 1 window, 9 spindles, 1 door, 1 full radiator, and all other trim	1,300 $
➢ Excludes repairs of baseboard cracks and installing the missing moulding on stringer [300$ - 400$]	[+ 300 $]
Dinning Room	**1,700 $**
➢ Preparation and painting of walls, 2 doorways and baseboards	950 $
➢ Includes preparation (2H) and painting of built-in shelf (excludes interior shelving)	400 $
➢ Includes preparation (1.5H) and painting of both sides of the arch-way to sun room	350 $
➢ Excludes popcorn ceiling and Breakfast Nook trim	
Breakfast Nook	**1,750 $**
➢ Includes all 10 windows, frames, benches and surrounding trim (excludes internal shelving)	1,750 $
➢ Excludes repairs to ensure smooth opening and closing of windows [.5H - 1H / window = 350$ - 750$]	[+ 500$]
➢ Excludes popcorn ceiling	
Basement Bathroom	**550 $**
➢ Includes walls and ceiling, door and window frame	450 $
➢ Includes skim coat to resurface repairs	100 $
ADD-ONS / EXTRAS / REPAIRS	
Estimated Cost of Repairs [2000$ - 3600$]	**[+2550 $]**
Painting of Dining Room popcorn ceiling	**1,000 $**
Painting of Breakfast Nook popcorn ceiling	**400 $**
TOTAL	**16,150 $**
TOTAL + PROJECTED REPAIRS	**18,700 $**
TPS # 7784757551RT0001	935.00 $
TVQ # 1231045518	1,865.33 $
GRAND TOTAL	**21,500 $**

PAINT AND PRODUCTS		
Our quotes include high-end exterior paint and all materials required for proper preparation of surfaces.		
WALLS: Sherwin Williams Duration Interior – excellent washability	Colour:	Oxford White CC-30 - Matte
TRIM: SW B53 – industrial grade, excellent durability	Colour:	Oxford White CC-30 - Semi-Gloss
CEILINGS: SW Promar 400 – ultra-flat paint	Colour:	Oxford White CC-30 - Ultra-Flat

DETAILS & MODALITIES					
PROPOSED START DATE	March 3rd	**DURATION OF WORK**	3 - 4 weeks	**DEPOSIT AMOUNT**	**$2,000**
Payment Method		The remaining balance is to be paid in cash, cheque or e-transfer, with installments spread out on a weekly basis throughout the work.			
All additional work will be charged accordingly. **This quote is valid for a period of 30 days.** **The client is responsable for ensuring that the work conforms to the specifications and permits required by the City.**					
Client Signature		OstéoPeinture Representative			

OSTÉOPEINTURE

#201 - 80 rue Saint-Viateur E., Montréal, QC H2T 1A6

438-870-8087 | osteopeinture@gmail.com

www.osteopeinture.com

RBQ# 5790-0045-01