OSTÉOPEINTURE

CLIENT	Susan Campbell	ADDRESS	570 Grosvenor Ave, Westmount
PROJECT	CAMPBELL_01	DATE	July 18th, 2025

DESCRIPTION OF WORK

HOME EXTERIOR REFRESH

OUR PRICE INCLUDES

- Proper preparation work, including primer where needed, and 2 coats of paint on all agreed upon surfaces
- Outdoor preparation includes cleaning of surfaces, chipping, and scraping of loose paint, caulking, and puttying
- Clean up at the end of each day, leaving the space clean
- Protection and safeguarding your property from construction damage
- A clean and respectful working environment to make the work period as smooth as possible for you
- Major repairs are excluded from the quote and will be charged at 65 $/h plus taxes and materials.

Given the nature of the exterior renovation work, please note that this is a realistic cost estimate, not a fixed price.
The final price will be billed based on the actual preparation time required for the work.

Front Entrance & Awning – preparation and painting (white surfaces only)	**1,250 $**
- Preparation incl. scraping loose paint, minor resurfacing, cleaning, priming, and caulking [approx. 650-950 $]	750 $
Main Cornice – preparation and painting	**2,850 $**
- Preparation includes scraping, grinding, thorough cleaning, and metal priming	2,000 $
- Includes full anti-rust treatment [exact scope to be confirmed on-site – approx. cost : 400$ - 1200$]	850 $
Top Flashing Cornice – preparation and painting	**500 $**
- Scope to be confirmed on-site. We must validate rust origin and overall condition.	
- Minimum – thorough clean & paint only [approx. cost : 450$]	
- Maximum – if rust anti-rust treatment required [approx. cost : 1000$]	
Three Side Window Frames – preparation and painting [approx. 300-400 $ / window]	**1,000 $**
- Preparation incl. scraping, sanding, cleaning, priming, and replacing the old caulking as required	
- [EXTRA] Potential wood repairs will be assessed on-site and charged separately	
Lift Rental	**1,850 $**
- Includes delivery, rental, and on-site setup	1,850 $
- Extra daily rental cost – applies if weather or unexpected repairs extend the rental period	[+550 $]
TOTAL	**7,450 $**
TPS # 7784757551RT0001	372.50 $
TVQ # 1231045518	743.14 $
GRAND TOTAL	**8,566 $**

PAINT AND PRODUCTS

Our quotes include high-end exterior paint and all materials required for proper preparation of surfaces.

White – Sherwin Williams Duration exterior paint or equivalent	Colour :	Off-White – TBD
Primer – ProCry industrial grade, galvanized metal primer	Colour :	Grey – Primer Base

DETAILS & MODALITIES

PROPOSED START DATE	**Week of July 21st**	**DURATION OF WORK**	**1 - 2 weeks**	**DEPOSIT AMOUNT**	**$2,000**
Payment Method	The remaining balance is to be paid in cash, cheque or e-transfer, with installments spread out on a weekly basis throughout the work.				

All additional work will be charged accordingly.
This quote is valid for a period of 30 days.
The client is responsable for ensuring that the work conforms to the specifications and permits required by the City.

Client Signature		OstéoPeinture Representative	Loïc St-Onge

OSTÉOPEINTURE
#201 - 80 rue Saint-Viateur E., Montréal, QC H2T 1A6
438-870-8087 | osteopeinture@gmail.com
www.osteopeinture.com
RBQ# 5790-0045-01