OSTÉOPEINTURE

CLIENT	Léa Girard & Harry Grivakis
PROJECT	GIRARD_01

ADDRESS	62 Rosemount Ave, Westmount
DATE	Nov 3, 2025

HOME REPAINT – Ground, 2nd, 3rd floors

SCOPE & TENTATIVE SCHEDULE

Phase	Start	Approx. Duration	End
Phase 1 – Primer & First Coats ➛ Protection of arches, doors, and bannisters from paint and damages ➛ Primer where needed (bare substrates or darker hues) ➛ Two coats on ceilings and crown moldings ➛ One coat on walls, doors, and trim	**Nov 17**	**3 weeks**	**Dec 5**
Phase 2 – Final Coats & Touch-Ups ➛ Protection of newly installed floors and staircase steps ➛ Final coat on walls and trim ➛ Two coats on newly installed trim (shoe mouldings) ➛ All touch-ups after flooring installation and cleaning	**Dec 15**	**5-7 days**	**Dec 24**

GENERAL CONDITIONS

➛ We take on protection of all woodwork and railings, removal of hardware (window pane handles, electrical plates, etc.)
➛ Primer & caulking where required
➛ We are not responsible for pre-existing cracks or defects that remain visible after painting
➛ Surfaces are ready to paint – i.e. plastering, sanding, and cleaning has been completed beforehand

COST BREAKDOWN

GENERAL	
Phase 1 – Initial set up & protection for spray (covering, installing dust barriers)	**1,500 $**
Phase 2 – Initial set up & thorough protection of all brand new floors	**1,000 $**
GROUND FLOOR	
Entrance	**450 $**
➛ Walls, ceiling, crown moulding & center medallion	450 $
Main Hall	**2,300 $**
➛ Walls, flat ceilings, 3 door frames, 1 radiator, 1 window	1,300 $
➛ Wainscoting – incl. caulking ~50 square panels	550 $
➛ Decorative paneled ceiling and crown moulding in semi-gloss finish	450 $

Powder Room & Small Hall	**1,400 $**
➛ Walls of small hall, both ceilings, all previously painted trim, 1 radiator, 1 door	1,000 $
➛ Incl. a dark color on powder room paneling and baseboards	400 $
➛ Excl. installation of wallpaper – to be validated based on wallpaper material and pattern choice	TBD
➛ Excl. closet and closet doors	
Formal Living Room	**3,500 $**
➛ Walls, ceiling, all previously painted trim, incl. 2 benches, 1 radiator, and primer on crown moulding	2,250 $
➛ All windows (13x panes, 1 circular) and their shutters (12x, external faces only)	1,250 $
➛ Incl. ceiling ornemental trim in semi-gloss finish	
Dining Room	**3,850 $**
➛ Walls, ceiling, crown moulding, 4 frames, 2 radiators – incl. primer on wainscoting and walls	1,850 $
➛ Wainscoting – incl. primer coat and caulking ~114 square panels	1,400 $
➛ All windows (9x panes), their shutters (4x, external faces only), inner trim and bench	600 $
Kitchen & Back Entrance	**750 $**
➛ Kitchen ceiling and 2 walls in sage color (client provides the paint)	550 $
➛ Back entrance ceiling, and 2 walls in sage color	200 $
Dark Pantry	**275 $**
➛ Ceiling, crown moulding and 1 small wall section (darker color, client provides paint)	275 $
Staircase	**1,450 $**
➛ Walls	275 $
➛ Wainscoting – incl. caulking of ~60 wainscoting square panels	750 $
➛ Incl. 1 window (3x panes, trim and frame) and all other staircase trim	425 $
➛ Excl. treads, risers, stringers, bannisters and railings	
➛ Excl. removal of handrails – includes patching the remaining holes	
2ND FLOOR	
Second Floor Hall	**2,125 $**
➛ Walls, ceiling, crown moulding & center medallion, 4 door frames	1,500 $
➛ Wainscoting – incl. caulking of ~40 square panels	500 $
➛ Incl. adjacent library ceiling in main ceiling white	125 $
Back Corridor & Closets	**850 $**
➛ Walls, ceiling, all previously painted trim, 1 radiator, 1 window – incl. mid-wall moulding in semi-gloss	850 $
➛ Excl. both closets	
Girl's Bedroom	**1,700 $**
➛ Walls and ceiling – incl. primer on walls and caulking joints between wooden trim and walls	950 $
➛ Incl. crown moulding in semi-gloss finish	400 $
➛ Incl. the walls behind the built-in shelving unit	350 $
Master Bedroom	**2,250 $**
➛ 3 walls, ceiling, all previously painted trim, incl. center medallion, and 1 radiator – incl. primer on all 4 walls	1,400 $
➛ Incl. crown moulding in semi-gloss finish	350 $
➛ Preparation (scraping, resurfacing, priming, caulking) and painting of window and trim [est. cost: 400-550$]	500 $
➛ Excl. installation of wallpaper – to be validated based on wallpaper material and pattern choice	TBD
Back room & Walk-in	**400 $**
➛ Both ceilings, excl. crown moulding	400 $

3RD FLOOR	
3rd Floor Hall & Staircase	**2,950 $**
➛ Walls, ceiling, crown moulding, 5 door frames & 1 window frame	1,950 $
➛ Wainscoting – incl. caulking of ~65 wainscoting square panels	850 $
➛ Staircase handrails	150 $
➛ Excl. treads, risers, stringers and bannisters	
SUBTOTAL	**26,750 $**
OPTIONAL ADD-ONS	
Master Bathroom – walls, ceiling, all trim incl. 3 windows, 2 doors	[+1350$]
Wallpaper installation	TBD
Benjamin Moore Aura paint instead of SW Emerald	[+450$]
SUBTOTAL APPROVED ADD-ONS	**0 $**
TOTAL	**26,750 $**
TPS # 7784757551RT0001	1,337.50 $
TVQ # 1231045518	2,668.31 $
GRAND TOTAL	**30,756 $**

PAINT AND PRODUCTS

Our quotes include high-end exterior paint and all materials required for proper preparation of surfaces.

Primer: SW PM200 primer	~ 175$	Main White, TBD – Semi-gloss
Ceilings: SW PM 400	~ 450$	Main White, TBD – Flat
Trim: SW B53 or equivalent	~ 1150$	Main White, TBD – Semi-gloss
Walls: SW Emerald	~ 1100$	Main White, TBD – Low Sheen
Sage / Dark paint for kitchen / pantry – to be provided by client		
approx. paint TOTAL (incl. in quote)	**~ 2875$**	

PAYMENT MODALITIES

DEPOSIT AMOUNT	**$2,500**	**PAYMENT METHOD**	The remaining balance is to be paid in cash, cheque or e-transfer, with installments spread out on a weekly basis throughout the work.

All additional work will be charged accordingly.
This quote is valid for a period of 30 days.
The client is responsable for ensuring that the work conforms to the specifications and permits required by the City.

Client Signature		OstéoPeinture Representative	

OSTÉOPEINTURE

#201 - 80 rue Saint-Viateur E., Montréal, QC H2T 1A6
438-870-8087 | osteopeinture@gmail.com
www.osteopeinture.com
RBQ# 5790-0045-01